

BID FORM

PROJECT: Chip Seal Various Road in Newton Twp, Licking County, Ohio

SCOPE: Single Chip Seal (#8 Limestone @ 25lbs/s.y. and RS-2 Seal @ .40 gal/s.y.)

ROAD NAME:

	<u>Road No.</u>	<u>Avg. Width ft</u>	<u>Length, ft</u>
Welsh Hills Rd (Newark Twp Line - Dry Creek) Suspend work (approx 175') at bridge	121	16	5375
Stickle Rd (CR 202 - Washington Twp Line)	251	18	3395
Swisher Rd (Martinsburg Rd - Mary Ann Twp Line)	257	18	1900
Claygate Lane (McKinney Crossing Rd - End)	1041	20	460
Rocky Ridge Rd, West (SR 13 - End), *	253	12	950
Hatfield Lane (SR 13 - End), *	1114	18	960

<u>QUAN.</u>	<u>UNIT</u>	<u>ITEM</u>	<u>DESCRIPTION</u>	<u>UNITS \$</u>	<u>TOTAL \$</u>
4,545	S.Y.	202	Wearing Course Removed	_____	_____
9,742	GAL.	422	RS-2 Seal @ 0.40 gal./s.y.	_____	_____
24,355	S.Y.	422	#8 Limestone @ 25 lbs./s.y.	_____	_____
20	Foot	642	Stop Line, Type 1	_____	_____
1	LUMP	614	Maintaining Traffic	_____	_____
1	LUMP	624	Mobilization	_____	_____
				TOTAL BID:	_____

- NOTES:**
1. Wearing Course Removed for the FEMA Limits per ODOT Std. Dwg. BP-3.1 for the following Locations.
 - a. Welsh Hills (Begin 950' South of Dry Creek Rd - End at Dry Creek Rd)
 - b. Swisher (Begin 680' East of Martinsburg Rd - End 1468' East of Martinsburg Rd)
 - c. Hatfield Lane (Begin 230' East of SR 13 - End 870' East of SR 13)
- * Requires Railroad coordination or Suspension of work and Stop Line

COMPANY: _____

ADDRESS: _____

SIGNATURE: _____

DATE: _____

Bid Breakdown by Road

Welsh Hills Road	\$ _____
Stickle Road	\$ _____
Swisher Road	\$ _____
Claygate Lane	\$ _____
Rocky Ridge Road	\$ _____
Hatfield Lane	\$ _____
TOTAL:	\$ _____